

15.009.00844.00.01

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Messman-Rinehart Corp.

Complete Address 1432 Vickers-KSB&T Bldg., Wichita, Kansas 67202

Lease Name Clarke Well No. 1

Location NE NE NE Sec. 22 Twp. 19 Rge. 14 ~~W~~ (W)X

County Barton Total Depth 3515'

Abandoned Oil Well X Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11:15 AM Day 11 Month 6 Year 1980

The above well was plugged as follows:

Sanded back to 1700' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 5 sx hulls,

15 sx mud gel, plug, and 125 sx cement.

Max. pres. 600#. Shut in pres. 350#.

Plugged back to 1860'. Top perforation at 1755'.

Recovered aprox. 1530' of 4 1/2" casing.

1901' of 4 1/2" casing cemented with 110 sx cement.

813' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 6-13-80  
INV. NO. 2355-w

Signed: Dean L Rankin  
Well Plugging Supervisor

6-13-80  
JUN 13 1980  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION