

15.009.00844.00.00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. NE NE NE

LOCATION NEC-NE/4

SEC. 22 TWP. 19 RGE. 14W-

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Walter Clark

Operator Ben F. Brack Oil Co., Inc. Address *310 Brown Bldg. Wichita, Kans.

Field _____ County Barton

Total Depth 3540 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 8 13/16 - Circulated with cement
5 1/2" casing set at 3511 ft - Filled back to 3500 ft
with chat - Pumped 5 sacks of cement at 3500 ft
Shot off & Pulled the 5 1/2" casing - Well flowing
salt water - Pumped in Plug & 250 sacks of
cement - Filling hole with cement from
815 ft up to the surface -
Cement Pumped in by Halliburton

PLUGGING
FILE SEC-28 T-19 R-14
BOOK PAGE-7 LINE-31

District Conservation Agent

Date 5-30-50