

State of Kansas



15.009.30318.00.00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

NOV 7 1966  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

11-7-66

Dear Sir:

Mr. Charles R. Mayfield of Mayfield & Smith Drlg., Inc. has this date requested permission to plug the following described well:

Mr. Pipe Pullers, Inc. guarantees payment of the plugging fee.

Operator's full Name: Mayfield & Smith Drilling, Inc.

Complete Address: Union Center Bldg., Wichita, Kansas

Lease Name: Meyeres "A" Well No. # 1

Location: SE SW SW Sec. 2 Twp. 17 Rge. 12 (E)(W) W

County Barton Total Depth 3391 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. C. B. Bradley was instructed to plug the well as follows:

8 5/8" 265' Cwc.

Sanded hole back to 3370' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mudded hole to 265'. set rock bridge, & displaced 4 sax cement with dump bailer. Let set-up. Bailed hole dry, displaced

21 sax cement. Mud to 40', set rock bridge, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don L. Swan  
Conservation Division Agent