

State of Kansas



15.009.30297.00.00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Thorton Anderson of High Plains Production Co. has this date requested permission to plug the following described well:

Mr. Thorton Anderson guarantees payment of the plugging fee.

Operator's full Name: High Plains Production Company

Complete Address: 304 Insurance Bldg., Wichita, Kansas 67202

Lease Name: Meyeres Well No.        # 1

Location: W/2 NE NW Sec. 2 Twp. 17 Rge. 12 (E)(W) W

County Barton Total Depth 3363 Oil Well X

Gas Well        Input Well        SWD Well        D & A        Lost Hole       

Mr. Walter Voth was instructed to plug the well as follows:

8 5/8" 264' Cwc.

Set bottom plug @ 3060' & dumped 5 sax cement with dump bailer. Pulled

pipe. Mudded hole to 260', set rock bridge, & dumped 5 sax cement.

Let set over night, bailed hole dry, & displaced 20 sax cement.

Mud to 40', set 10' rock bridge, & displaced 10 sax cement, cementing

to base of cellar.

Very truly yours,

Don Luman  
Conservation Division Agent