



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 11 1962

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Dwight J. Wilson of Alpine Oil & Royalty Co. has this date requested permission to plug the following described well:

Mr. Dwight J. Wilson guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Benjamin "A" Well No. # 2

Location: SE SW NE Sec. 3 Twp. 19 Rge. 13 (E) (W)

County Barton Total Depth 3393 Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Ralph Glenn was instructed to plug the well as follows:

8 5/8" 200' Cwc. Artesian brime.

Sand hole back to 3145' & dump 4 sax cement with dump bailer.

Full pipe. Squeeze hole with 10 sax mud & 80 sax cement with

Sun Cementing Company's pump truck, cementing from 250' to

base of cellar.

Very truly yours,

[Signature]
 Conservation Division Agent