



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging ~~Well~~ <sup>State</sup>)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Icer Addis guarantees payment of the plugging fee.

Operator's full Name: Icer Addis

Complete Address: Drawer 8083, Wichita, Kansas 67202

Lease Name: Berchek Well No. # 1

Location: W/2 SE SE Sec. 1 Twp. 19 Rge. 13 (E)(W)W

County: Barton Total Depth 3372 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Larry Curtis was instructed to plug the well as follows:

8 5/8" csg. 300' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 290' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Halliburton Cementing Company's pump truck, cementing

to base of cellar.

Very truly yours,

Don Luman  
Conservation Division Agent