

State of Kansas



15.009.30482.00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

STATE CORPORATION COMMISSION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

NOV 19 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Michael of Sage Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Three G Oil Co., Inc. guarantees payment of the plugging fee.

Operator's full Name: Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza, Wichita, Kansas

Lease Name: Berchek Well No. # 1

Location: W/2 SE SE Sec. 1 Twp. 19 Rge. 13 (E)(W) W

County Barton Total Depth 3423 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clarence Michael was instructed to plug the well as follows:

8 5/8" 280' Cwc.

Filled hole with heavy mud to 250', set plug with 1/4 sax hulls, & displaced

25 sax cement thru drill pipe. Mud to 40', 1/4 sax hulls, plug, & dis-

placed 10 sax cement, cementing to base of cellar.

Very truly yours,

Don [Signature]
Conservation Division Agent