

State of Kansas



FORM CP-2

15.009.00399.00.01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Wenrich of Murfin Drlg. Co. has this
date requested permission to plug the following described well:

Mr. Wenrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Co.

Complete Address: 617 Union Center, Wichita, Kansas 67202

Lease Name: Spanier (Formerly Miller) Well No. 1

Location: SE SE SE Sec. 16 Twp. 19 Rge. 12 (S) (W) X

County: Barton Total Depth 3503' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wenrich was instructed to plug the well as follows:

Fill hole with mud and spot 40 sx cement at 500'.

Fill hole with mud and spot 25 sx cement at 230'.

Fill hole with mud to 40' and $\frac{1}{2}$ sx hulls, plug, and

10 sx cement. 2 sx cement in rat hole.

237' of 8 5/8" surface casing cement circ.

Very truly yours,

Duane L Rankin
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1979
CONSERVATION DIVISION
Wichita, Kansas