

State of Kansas



15.009.20279.00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Frank Neff of Nadel & Gussman has this date requested permission to plug the following described well:

Mr. Nadel & Gussman guarantees payment of the plugging fee.

Operator's full Name: Nadel & Gussman

Complete Address: 1714 First Nat'l Bldg. ^{Tulsa, Oklahoma} ~~Wichita, Kansas~~

Lease Name: Bieberle Well No. # 4

Location: SW NW NE Sec. 15 Twp. 18 Rge. 11 (E)(W) W

County: Barton Total Depth 3360 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Frank Neff was instructed to plug the well as follows:

8 5/8" 267' Cwc.

Circulated hole with heavy mud to 450', set plug, & displaced 40 sax cement thru drill pipe. Mud to 260' & displaced 25 sax cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with Allied Cementing Company's pump truck, cementing to base of cellar.

STATE CORPORATION COMMISSION

OCT 8 - 1968

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

[Signature]
Conservation Division Agent