

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas**

Barton County, Sec. 14 Twp. 16 Rge. 15 (E) (W)

If a producing well is abandoned, date of last production..... NO 19.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?..... Yes

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Hole filled with heavy mud 3543 to 200 feet -
15 sacks cement at 200' - top plug @ 40' with
10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Nadel and Gussman
Address P. O. Box 309, Tulsa, Oklahoma

STATE OF KANSAS COUNTY OF SEDGWICK ss.

L. C. Hay (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

SUBSCRIBED AND SWORN to before me this 16th day of October 1950

My commission expires.....Nov. 3, 1952

28-8278-S 4-50-10M

PLUGGING
FILE SEC. 14 T-16 R (90)
BOOK PAGE 35 LINE 13

WELL LOG

15.009.00482.00.00

NADEL AND GUSSMAN

KARST No. 1

SW SW NW 14-16-15W
Barton County, KansasComm. 9-29-50
Comp. 10-12-50CASING RECORD: 8-5/8" @ 200¢
Cement 115 Sars

Formations

Depth

Shale and sand	30
Shale and shells	202
Shale and shells and Red bed	535
Sand	640
Shale and red bed	800
Shale, shells and sand	1010
Anhydrite	1050
Shale and shells	1435
Shale and salt	1500
Shale	1700
Shale and lime	1790
Broken lime	1975
Lime and shale	2070
Lime	2155
Shale	2225
Shale and Lime	2608
Shale and shells	2837
Lime	3219
Shale	3229
Lime	3443
Lime and shale	3473
Lime	3480
Conglomerate	3508
Arbuckle	3543
D&A	

Geological Tops

Heebner	3170
Toronto	3190
Lansing	3229
Conglomerate	3483
Arbuckle	3502

STATE OF KANSAS

COUNTY OF SEDGWICK


SS

L. C. Hay, of lawful age, deposes and states that the above depths and formations are true and correct as taken from the ~~existing~~ daily drilling log, covering the Karst No. 1 in the SW SW NW 14-16-15W Barton County, Kansas.

Subscribed and sworn to before me this 16th day of October, 1950

RECEIVED
STATE CORPORATE COMMISSION
Notary Public

My commission expires Nov. 8, 1952 OCT 1 1950



CONSF