

OSCAR KARST NO. 1

Spudded: 11/17/40
Drilling Completed: 12/7/40
Date Plugged: 12/9/40

Location: 330' South and 990' West
of North 1/4 Corner of Sec. 12, Twp.
16S, Rge. 15W, Barton County, Kansas

From	To	Formation	From	To	Formation
0	30	Surface	2467	2555	Shale & shells
30	317	Shale & surface sand	2555	2684	Shale & lime
317	420	Surface sand	2684	2711	Lime
420	652	Sand & red beds	2711	2845	Shale & lime
652	935	Red rock	2845	2875	Shale & shells
935	1245	Red rock & shale	2875	3024	Lime
1245	1595	Shale	3024	3080	Shale & lime
1595	1712	Shale & shells	3080	3225	Lime
1712	1883	Lime & shale	3225	3275	Shale & lime
1883	1983	Shale & lime	3275	3323	Shale & lime
1983	2162	Lime	3323	3361	Lime & shale
2162	2232	Shale & shells	3361	3407	Lime
2232	2467	Lime	3407	3418	Conglomerate
			3418	3423	Lime

Elevation from derrick floor level 1917'

Run 408'2" of 10-3/4"OD 40# 8-thd lapweld surface casing; set at 402'; cemented with 225 sacks of cement.

* Top of K. C. Lime 3159' - Show of oil from 3253' to 3256' - Coming out of hole with drill pipe to core.
12/5/40 - Core No. 1- Cored from 3256' to 3271' - Recovered 2' of hard white lime - No show - Small stain of oil in sample cuttings from 3256' to 3262'.

** Top of Arbuckle Lime 3411'
12/7/40 - Core No. 2- Cored from 3414' to 3419' - Recovered 3' of Arbuckle Line spotted with dead oil - Show of sulphur water.
Run Schlumberger Survey, slight show of oil from 3448' to 3458' - No show of oil in Arbuckle Line.
Total depth 3419'

12/9/40 - Plugged and abandoned.

* Top of K. C. Lime and coring in K. C. Lime calculated from top of rotary table.

** Top of Arbuckle Lime, coring in Arbuckle Line, Schlumberger Survey and total depth calculated from ground level.

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

F. L. D...
Name and title of representative of company

Subscribed and sworn to before me this the 17th day of December, 1940.

My Commission expires October 21, 1944 Lewis M. K...
Notary Public

FLD-JL 12/17/40
LPC (3)-
File (1)

12 16 15W
124 27

TALLY BOOK

Tsf. No. _____ Date 11-17 19 40

From Conico Replaced Not Replaced

Used For _____

To Oscar Knst #1 Replacement New Work

Used For AZE #8928

Size 10 3/4 Wt. 40 # Thd. 8 Cond. B

Car No. _____ Initial LW Manu. _____

FEET	IN.	FEET	IN.	FEET	IN.	FEET	IN.	FEET	IN.
17	9	19	9						
21	11								
18	1								
19	3								
18	11								
18	8								
19	4								
18	11								
19	7								
17	9								
20	1								
19	7								
19	11								
20	7								
18	11								
19	7								
19	8								
17	4								
20	7								
20	-								
386	5	19	9						

19-9 Hauled by _____
 Talled by J. D. O'Neal
 Foreman _____ Hd. Rst. _____
 Remarks _____
406-2