

Strike out upper line when reporting plugging off formations.

NORTH

**Locate well correctly on above
Section Plat**

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines **330'S & 330'W of NE Corner**

Location as NE 1/4 NW 1/4 of 100 acre from line.

Lease Owner: **Continental Oil Company**

Lease Name **John Miller** Well No. **1**

Office Address **Box 1267, Ponca City, Oklahoma**

Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**

Date well completed..... July 6, 1942

Application for plugging filed July 7, 1942

Application for plugging approved..... July 7, 1942

Plugging commenced..... July 7, 1942

Plugging completed..... July 7, 1942

Reason for abandonment of well or producing formation **Dry Hole**

Reason for abandonment or well or producing formation.....

If a producing well is abandoned, date of last production	None	10
---	------	----

Was permission obtained from the Conservation Division or its agents before plugging was completed? ☐ Yes ☐ No

Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**

Name of Conservation Agent who supervised plugging of this well Mr. C. T. Alexander, Great Bend, Kansas

Producing formation Arbuckle Lime Depth to top 3464' Bottom 3473' Total Depth of Well 3473 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

The hole was filled with heavy mud to within 365' of the top, a wood plug was set and the hole bridged with rock and 15 sacks of cement to within 335' of the top, the hole was then filled with heavy mud to within 26' of the top, a wood plug was set and the hole bridged with rock and 10 sacks of cement to within 8' of the top, the hole was then filled with heavy mud to the top and a steel cap welded over the top of the surface pipe.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Continental Oil Company, c/o F. L. Dunn
Address R. F. D. #4, Lyons, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
F. L. Dunn (employee of owner) or (owner or operator) of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

R. F. D. #4, Lyons, Kansas

SUBSCRIBED AND SWORN to before me this 25th day of July 1942

My commission expires.....October 21st, 1944

.....
Notary Public.

TALLY BOOK

Tsf. No. _____ Date 6-25 1942

From _____ ☐ Replaced
☐ Not Replaced

Used For _____

To John Miller #1 ☐ Replacement
☒ New Work

Used For Surfing Pipe

Size 10 3/4 Wt. 25# Thd. 3ga. Cond. None

Car No. _____ Initial _____ Manu. _____

"Amco" Spin Weld Casing

FEET	IN.	FEET	IN.	FEET	IN.	FEET	IN.	FEET	IN.
40	-								
40	-								
40	-								
40	-								
40	-								
40	-								
40	-								
40	-								
40	-								
40	-								
360	0								

Hauled by _____

Tallied by _____

Foreman _____ Hd. Rst. _____

Remarks FILE 21 16 140

360-0

BOOK

PAGE 41 3