

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD 15.009.30909.00.01  
K.A.R.-82-3-117

API NUMBER Completion 11-17-69

LEASE NAME Turgeon

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 9 TWP. 16S RGE. 12W (E) or (W)

COUNTY Barton

Date Well Completed         

Plugging Commenced 8-17-93

Plugging Completed 8-19-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS RR1, Box 183B, Great Bend, KS 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil (OWWO)

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3262'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	806'	none
				5 1/2"	3262'	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          foot each set.  
Sanded bottom to 3007' & 5 sks cement. Shot at 2500', worked pipe free. Spotted 90 sks @ 1660' w/200# hulls. Spotted 25 sks @ 830' w/100# hulls. Spotted 50 sks @ 450' w/100# hulls. Pulled casing, spotted 10 sks to fill 8 5/8" to surface. 60/40 pos 10% gel. Plugging complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

AUG 25 1993

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 93

          
Notary Public

My Commission Expires:         

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 1993