

15.009.14174.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD

Barton County, Sec. 4 Twp. 16 Rge. 13 (E) W (W)

Location as "NE/CNW/SE" or footage from lines W/2 SW SE

Lease Owner Shields Oil Producers, Inc.

Lease Name Deutsch "A" Well No. 1

Office Address Shields Bldg., Russell, Kansas 67665

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed May 6 1978

Application for plugging filed May 6 1978

Application for plugging approved May 6 1978

Plugging commenced May 6 1978

Plugging completed May 6 1978

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 10

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Duane Rankin

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,425 Feet

Show depth and thickness of water, oil and gas formations.

OIL, GAS AND WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	876'	Cmtd.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole w/heavy mud
Push bridge plug to 400'
Pump 50 sax cement on plug thru 4 1/2" drill pipe
Push bridge plug to 40' w/1/2 sax hulls on plug
Dump 10 sax cement on plug to cellar
Dump 4 sax cement in rat hole and mouse hole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shields Drilling Co., Inc.

Address Shields Bldg., Russell, Kansas 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

R.L. Shields (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.L. Shields
Shields Bldg., Russell, Kansas

SUBSCRIBED AND SWORN to before me this 2nd day of August 1978

My commission expires May 26, 1979
Ruth Phillips Notary Public.



Shields


15.009.14174.00.00

Russell, Kansas

WELL LOG

Operator: Shields Oil Producers, Inc.
Well: Deutsch "A" #1
Commenced:
Completed:
Contractor:

Well Description: W/2 SW SE
Sec. 4-16S-13W
Barton Co., Kansas



Elevation: 1,906' KB

Treatment:

Production: D & A

Tops: Heebner 3,034'
Brown Lime 3,117'
Lansing-KC 3,128'
Arbuckle 3,363'

CASING RECORD

Size	Run	Pulled
8 5/8"	876'	Cmtd.

..... Figures Indicate Bottom of Formations

This hole was originally drilled by Sunray-DX in 1946. No well log is available of the original hole.

RECEIVED
STATE CORPORATION COMMISSION
AUG 03 1978
CONSERVATION DIVISION
Wichita, Kansas

Notes