

State of Kansas



15-159-30327-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 21, 1967

RECEIVED  
STATE CORPORATION COMMISSION

FEB 24 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ray Rice of Group Exploration Co. has this

date requested permission to plug the following described well:

Mr. Rice guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company & Sterling Drilling Company

Complete Address: Box 129, Sterling, Kansas 67579

Lease Name: Dill Well No. 1

Location: SW NE NW Sec. 29 Twp. 21 Rge. 8 (E) (W) X

County Rice Total Depth 3596' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rice was instructed to plug the well as follows:

Fill hole with mud to 215'. Push plug and 1/4 sack hulls to 215' and

cement hole with 25 sacks cement through drill pipe. Fill hole with

mud to 40'. Push plug and 1/4 sack hulls to 40' and cap hole with 10

sacks cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

  
Conservation Division Agent