



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

October 22, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walt Coldwater of Alpine Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Coldwater guarantees payment of the plugging fee.

Operator's full Name: Alpine Drilling Company, Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas 67202

Lease Name: Pearson Well No. 1

Location: C NW NW Sec. 33 Twp. 21 Rge. 8 (X) (W) X

County: Rice Total Depth 3650' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Coldwater was instructed to plug the well as follows:

Fill hole with mud to 250'. Push plug and 1/4 sack hulls to 250' and cement hole with 25 sacks cement through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent