



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION
(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
OCT 2 - 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 19, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ed. Schonoff of Pipe Pullers, Inc. has this
date requested permission to plug the following described well:

Mr. Schonoff guarantees payment of the plugging fee.

Operator's full Name: H. L. Herbel

Complete Address: P.O. Box 327, Chase, Kansas 67524

Lease Name: C. R. Frederick Well No. 2

Location: SE NW Sec. 36 Twp. 21 Rge. 8 (E) (W) X

County: Rice Total Depth 3495' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schonoff was instructed to plug the well as follows:

Push 5 1/2" plug to 3350'. Fill hole with sand to 3340' and cement hole
with 5 sacks. Fill hole with mud to 260'. Set rock bridge from 260'
to 250' and cement hole with 25 sacks. Fill hole with mud to 40'.
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent