

15.009.01335.00.00
WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

A 4x4 grid with a small circle in the bottom-right cell.

Locate well correctly on above
Section Plat



OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

T.D. 3496'. 5 $\frac{1}{2}$ casing set at 3465. Dumped 5 sacks of cement at 3496' Top of cement 3453'. Filled hole with heavy mud from 3453 to 250'. Dumped 10 sacks cement, filled with heavy mud to 10' dumped 10 sacks of cement for cap.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to.....W.L. Hartman
Address.....P.O. Box 54 Wichita 1 Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. T. Phoenix (employee of owner) or ~~(owner or operator)~~ of the above-described well,
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Ellinwood Kansas.

.....
(Address)

SUBSCRIBED AND SWORN to before me this 14 th day of February, 19 46

My commission expires July 7, 1948

.....
Notary Public.

15,009.01 335.00.00

Company - W. L. Hartman
 Contractor - Virginia Drilling Co. Inc.
 Commenced - October 22, 1945
 Completed - December 17, 1945
 Total Depth - 3483
 Elevation - 1854

FORMATIONDEPTH

Soil and sand	0- 112	<u>TOPS:</u>	
Iron	112- 131		
Iron-Red Chert	131- 133	Topoka	2774
Shale	133- 152	Hubnershale	3086
Sand-iron	152-160	Lansing-KC brown lime	3197
Broken lime-iron	160- 243	White Lime	3218
Red bed-sand	243- 324	Conglomerate	3445
Red bed	324- 420	Arbuokle	3464
set 336' of 8 5/8" sur. cas.			
Red bed-shale	420-680		
Shale-shells-anhrdrite	680- 785	CIRC. @ 3311	--1 hr.
Shale-shells	785-1175	3441	1 1/2 hr.
Salt-shale-shells	1175-1320	3446	1 1/2 hr.
Shale-salt	1320-1385	3452	1 1/2 hr.
Lime-shale	1385-1630	3457	1 hr.
Lime, rough	1630-1730	3463	1 1/2 hr.
Lime	1730-2075	3466	5 hr.
Lime-shale	2075-2160		
Lime-shale	2160-2270		
Shale-shells	2270-2380		
Shale-lime	2380-2505		
Shale-sand	2505-2580		
Br. lime	2580-2640		
Lime	2640-2700		
Lime-shale	2700-2765		
Lime	2765-2925		
Lime-shale	2925-2975		
Lime	2975-3035		
Lime-shale	3035-3047		
Lime	3047-3165		
Shale	3165-3218		
Lime	3218-3410		
Lime-shale	3410-3466		
Drilled	3466-3483		
T.D.	-3483		
108 jts. 5 1/2" O.D. set at	-3465		

Total 12 hrs.-15 min.

Now comes S. A. Murphy, who states that he is familiar with the drilling of oil and gas wells and knows of his own knowledge that the Selle # 1 located in the NECr SE/4 of Section 10-20S-13W Barton County, Kansas was drilled to a total depth of 3483 feet. ~~Same being planned and abandoned.~~

PLUGGING	
FILE	10-20S-13W
BOOK	PAGE 42 ENC-1-6

Subscribed and sworn to before me, a Notary Public this 27th day of December, 1945.

S. A. Murphy
 Notary Public

My commission expires: February 5, 1949.