

R

15.009.00482.00.01

CP-3

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: Route # 2, Great Bend, Kansas

Lease Name Karst Well No. 1

Location SW SW NW Sec. 14 Twp. 16 Rge. 15 (E) (W)

County Barton Total Depth 3542

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Washdown

Plugging Contractor: Garvey Drilling Company

Address: Route # 2, Great Bend, Kansas License No.

Operation Completed: Hour 9:30AM Day 3 Month 7 Year 1962

The Above well was plugged as follows:

8 5/8" 200' Cwc.

Filled hole with heavy mud to 300'; set plug and displaced 20

sax cement thru drill pipe. Mud to 190'; set plug with 1/4 sax hulls;

and displaced 20 sax cement thru drill pipe. Mud to 35'; 1/4 sax hulls,

plug; and displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Truman
Well Plugging Supervisor