


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County. Sec. 33 Twp. 21S Rge. 8W
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Mrs. J. D. Zimmerman
Lease Name FEE Well No. 1
Office Address 128 W Main, Sterling, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-4 19 61
Application for plugging filed 3-4 19 61
Application for plugging approved 3-4 19 61
Plugging commenced 3-4 19 61
Plugging completed 3-4 19 61
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	258'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud to 250', Halliburton plug at 250' with 20 sacks cement through drill pipe. Heavy mud to 35', Halliburton plug at 35' with 10 sacks cement to base of cellar.

STATE CORPORATION COMMISSION
MAR 8 1961
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sterling Drilling Company
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
F. A. Wuellner, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner, Secretary
Sterling, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1961

My Commission Expires Jan. 22, 1962

Bernard Landermilk
Notary Public.

My commission expires



15.159-00435-0000

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1961

STERLING DRILLING COMPANY
Sterling, Kansas

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG -----ZIMMERMAN FEE #1

Located: C SE NE, Section 33-21S-8W, Rice County, Kansas

OWNER: Mrs. J. D. Zimmerman & Sterling Drilling Company

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 2-25-61

COMPLETED: 3-4-61

ROTARY TOTAL DEPTH: 3378'

LOG

0	-	70	Sand & Shale
70	-	259	Sand & Red Bed
259	-	365	Red Bed & Shale
365	-	1085	Shale
1085	-	1395	Shale & Lime
1395	-	1930	Lime
1930	-	2475	Shale
2475	-	2695	Lime
2695	-	2900	Lime & Shale
2900	-	2955	Shale
2955	-	3305	Lime
3305	-	3342	Shale & Lime
3342	-	3364	Coring & Reaming
3364	-	3378	Shale & Lime T.D.

CASING RECORD

Set 8-5/8" Surface Casing @ 258'
with 275 sacks cement.

Plugged and Abandoned

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG -----ZIMMERMAN FEE #1
Located: C SE NE, Section 33-21S-8W, Rice County, Kansas

OWNER: Mrs. J. D. Zimmerman & Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 2-25-61
COMPLETED: 3-4-61

ROTARY TOTAL DEPTH: 3378'

LOG

0	-	70	Sand & Shale
70	-	259	Sand & Red Bed
259	-	365	Red Bed & Shale
365	-	1085	Shale
1085	-	1395	Shale & Lime
1395	-	1930	Lime
1930	-	2475	Shale
2475	-	2695	Lime
2695	-	2900	Lime & Shale
2900	-	2955	Shale
2955	-	3305	Lime
3305	-	3342	Shale & Lime
3342	-	3364	Coring & Reaming
3364	-	3378	Shale & Lime T.D.

CASING RECORD

Set 8-5/8" Surface Casing @ 258'
with 275 sacks cement.

Plugged and Abandoned

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1961
CONSERVATION DIVISION
Wichita, Kansas