

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rice County, Sec. 26 Twp. 21S Rge. 7 (E) 7 (W)

Location as "NE/CNW&SW" or footage from lines C NW NW

Lease Owner C & J Oil Company

Lease Name Huffman Well No. 1

Office Address Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed February 8 19 69

Application for plugging filed Jan. 16 19 71

Application for plugging approved Jan. 18 19 71


Plugging commenced January 26 19 71

Plugging completed February 3 19 71

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3432 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3429'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Well plugged back to 3400', dumped 5 sacks cement;  
set bridge at 225' to 200', dumped 4 yards ready mix concrete.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 24 1971  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_

Address \_\_\_\_\_

STATE OF Kansas, COUNTY OF Barton, ss.

Robert L. Pelster (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]


Robert L. Pelster, Great Bend, Kansas

(Address)

Subscribed and sworn to before me this 19th day of February, 19 71

April 18, 1972

Notary Public.



XERO COPY

XERO COPY

XERO COPY

XERO COPY

*File*

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- HUFFMAN #1  
LOCATED: C NW NW, Section 26-21S-7W, Rice County, Kansas

OWNER: C and J Oil Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 3, 1969  
COMPLETED: February 8, 1969

TOTAL DEPTH: 3432'

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1971  
CONSERVATION DIVISION  
Wichita, Kansas

LOG

CASING RECORD

0 - 65	Sand
65 - 100	Shale Red
100 - 175	Shale and Shells
175 - 1190	Shale
1190 - 1562	Shale and Shells
1562 - 1990	Shale
1990 - 2900	Lime and Shale
2900 - 3432	Lime

Ran 4 joints 8 5/8" casing, 161.40'  
cemented at 173' K.B. with 190 sacks  
HA-5. Plug down @ 11:00 PM, 2-3-69.

Ran 88 joints 5 1/2" casing (3443.28')  
Set @ 3429' K.B. with 75 sacks salt  
saturated cement. Plug down @ 9:30 AM,  
2-8-69.