

15.009.01318.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County. Sec. 6 Twp. 17 Rge. (E) 11 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE/4 NE/4 NW/4
Lease Owner. The Derby Oil Company
Lease Name. Zorn Well No. 1
Office Address. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. March 6 1945
Application for plugging filed. March 10 1945
Application for plugging approved. March 21 1945
Plugging commenced. April 9 1945
Plugging completed. April 12 1945
Reason for abandonment of well or producing formation. Not Productive
If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr
Producing formation. None Depth to top. Bottom. Total Depth of Well. 3360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	265	None
				5-1/2"	3094	2481

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 12 sacks cement at 3064'. Top of cement 2975'
Shot 5 1/2" casing at 2600' 2550'. Pulled 25 joints.
Plugging hole with heavy mud through 5 1/2" pipe
Plugging hole with heavy mud through 5 1/2" pipe.
Finished pulling pipe.
Set permanent bridge at 250'. Dumped 15 sacks cement
Top of cement at 220'. Filled hole with heavy mud to
10' of top. Mixed 5 sacks cement for cap.

6 17 11 AM
6 27

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Derby Oil Company
Address Wichita, Kansas

5445

STATE OF Kansas COUNTY OF Sedgwick ss.

S. E. Banks (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. E. Banks

Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May 1945.

My commission expires July 31, 1947

[Signature]
Notary Public.

15.009.01318.00.00

THE DERBY OIL COMPANY

Record of Well No. 1

Farm: F. Zorn

Location: NE NW

Sec. 6 Twp. 17 Rge. 11W

Contractor: Kiowa Drilling Co.

County: Barton

Drilling Commenced: 2-13-45

State: Kansas

Elevation: 1863

Drilling Completed: 3-6-45

CASING RECORD

size	feet	kind	weight
8 5/8"	265'		28#
5 1/2"	3094'		14#

125 sx. Cem.
7 1/2 sx. Cem.

Formation	Bottom	Formation	Bottom
Surface	0- 193		
Shale	265		
Shale & Shells	1508		
Lime & Shale	1830		
Lime	1888		
Lime & Shale	2455		
Lime Broken	2500		
Lime	2595		
Shale & Lime	2770		
Lime	3313		
Conglomerate	3333		
Lime	3360		

GEOLOGICAL SURVEY

Tops:

Douglas zone	2983'
Lans.	3056'
Arb.	3331'
Total Depth	3360'

good sho oil & gas 2983-89.
Perf. 36/2981-93 - 4 gal wtr. per hour.
no sho

D&A

6 17 11W
6 27

