

15.009.20305.00.00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 2 Twp. 17S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines NE SW NE
Lease Owner Black Dot Oil Co., Inc.
Lease Name Burmeister Well No. 1
Office Address 538 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed 11-21 19 68
Application for plugging filed 11-21 19 68
Application for plugging approved 11-21 19 68
Plugging commenced 11:30 P.M. 11-21 19 68
Plugging completed 1:45 A.M. 11-21 19 68
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Don Truan - Russell, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3433 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Soil Clay & Shale		0	328	8 5/8	328	0
RECEIVED STATE CORPORATION COMMISSION NOV 27 1968 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole - Ran 325' Drill pipe & plug
Cemented thru drill pipe w/25 sx
Fill hole to 40' plug & hulls w/10 sx - 2 sx in rat hole.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor B & B Drilling, Inc.
Address 207 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Lahar
207 Petroleum Bldg. Wichita
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of November, 19 68

My commission expires May 31, 1970

Alma A. Neis
Notary Public.

15.009.20305.00.00

B & B DRILLING, INC.

548 Petroleum Building
Wichita, Kansas 67202

November 26, 1968

DRILLERS LOG

Re: Burmeister #1
NE SW NE Sec. 2-17S-11W
Barton County, Kansas

COMPANY: Black Dot Oil Company, Inc.
CONTRACTOR: B & B Drilling, Inc.
TOTAL DEPTH: 3433'
COMMENCED: 11-13-68
COMPLETED: 11-21-68

0	329	Soil, Clay Shale
329	371	Soil, Clay Shale
371	743	Clay & Shale
743	771	Anhydrite
771	1097	Shale & Shells
1097	1452	Shale
1452	1560	Lime & Shale
1560	1925	Lime & Shale
1925	2255	Shale & Lime
2255	2513	Lime & Shale
2513	2715	Shale & Lime
2715	3090	Lime & Shale
3090	3145	Lime
3145	3154	Lime - DST #1
3154	3305	Lime
3305	3385	Lime
3385	3402	Lime - Cong.
3402	3414	Arb. DST #2
3414	3419	Arb. DST #3
3419	3426	Arb.
3426	3433	Arb. DST #4
3433		DST #5 Total Depth D & A

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1968
CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Burmeister, located in Barton County, Kansas

Bill Baker President

Alma A. Meier Notary Public

Subscribed and sworn to before me
this 26th day of November, 1968
My commission expires May 31, 1970