


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15.009.01122.00.00
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barton County. Sec. 8 Twp. 17 Rge. 11W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Bennett & Roberts Oil Operations
Lease Name Kirmer Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/3 19 58
Application for plugging filed 11/3-verbally 19 58
Application for plugging approved 11/3-verbally 19 58
Plugging commenced 11/3 19 58
Plugging completed 11/3 19 58
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3380 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	300'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud up to 280' - 1/4 sack hulls - 1 plug & 25 sacks cement.
Mud up to 40' - 1/4 sack hulls, 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1958

My commission expires 6/17/62 Marvin Hummel Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
NOV 7 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 8 TWP. 17 R. 11W
BOOK PAGE 143 LINE 33

Bennett & Roberts Oil Operations
Kirmer #1

SW SW SW of Sec. 8-17-11W
Barton County, Kansas

R.T.D. 3380

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Commenced 10/27/58
Completed 11/3/58

8 5/8" Set @ 300' w/175 sx cmt.

Surface Soil & Clay	40
Clay	60
Sand	90
Gray Shale & Clay	300
Shale & Shells	485
Red Bed & Shale	730
Anhydrite	770
Red Bed, Shale	1270
Shale & Shells	1380
Shale & Lime Streaks	1550
Shale & Lime	1775
Lime	1910
Lime & Shale	2918
Lime	3380

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is true and correct to the best of my knowledge.

BENNETT & ROBERTS OIL OPERATIONS

By John R. Quinn

Subscribed and sworn to before me this 5th day of November, 1958.

Clara Hummel
Notary Public

My Commission Expires 6/17/62

STATE OF KANSAS
STATE CORPORATION COMMISSIONER

NOV 7 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING	
FILE SEC.	8 T. 17. R. 11W
BOOK PAGE	143 LINE 33