

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22773-00-00
Spot: E2W2NESW Sec/Twnshp/Rge: 30-11S-21W
1980 feet from S Section Line, 1700 feet from W Section Line
Lease Name: NILHAS TRUST Well #: 1-30
County: TREGO Total Vertical Depth: 4094 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1515 WYNKOOP, STE 700
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4082		180 SX
SURF	8.625	350		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2017 10:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: KEVIN Company: SAMUEL GARY JR. & ASSOCIATES Phone: (785) 421-7321

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/400 # hulls and 14 sx gel.
Perforations: 3882' - 3904'.
Port Collar at 1780' w/130 sx cement.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2017 1:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3856' and pumped 14 sx gel followed by 65 sx cement w/250 # hulls. Pulled tubing to 1825' and pumped 180 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 15 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.06510 -099.69802

Perfs:

Top	Bot	Thru	Comments
3882	3904		


INVOICED
JUN 27 2017

Remarks: QUALITY CEMENT TICKET # 239

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

JUN 02 2017

RECEIVED

MAY 25 2017