

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21960-00-00
Spot: SESENW Sec/Twnshp/Rge: 9-14S-13W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PRICE Well #: 1
County: RUSSELL Total Vertical Depth: 2490 feet

Operator License No.: 34278
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C
Address: 18529 WALTERS RD PO BOX 606
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2477		60 SX
SURF	7	511		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2017 9:00 AM
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: SHAWN D. EVANS INC. DBA ACE Phone: (620) 786-5514

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/100 # hulls.
CIBP at 2437'.
Alt II- Allied circulated 150 sx cement from 1250 on 4 1/2" casing.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2017 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2334' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1200' and pumped 65 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 15 sx cement at 300 psi. Casing and braden head full of cement.

GPS: 38.85022 -098.77291

Perfs:

Top	Bot	Thru	Comments
2393	2402		
2372	2383		

INVOICED
JUN 27 2017

Remarks: QUALITY CEMENTING TICKET # 023

Plugged through: TBG

District: 04

Signed

Ray Dinkel

KCC WICHITA

(TECHNICIAN)

CM

JUN 22 2017

RECEIVED