

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-21972-00-01
Spot: NWNEENESW Sec/Twnshp/Rge: 9-14S-13W
2317 feet from S Section Line, 3055 feet from E Section Line
Lease Name: PARKHURST Well #: 2
County: RUSSELL Total Vertical Depth: 2490 feet

Operator License No.: 34278
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C
Address: 18529 WALTERS RD PO BOX 606
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2490		75 SX
SURF	8.625	257		175 SX

Well Type: EOR UIC Docket No: E23801.1 Date/Time to Plug: 05/09/2017 1:30 PM
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: SHAWN D. EVANS INC. DBA ACE Phone: (620) 786-5514

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/100 # hulls.
Cement ticket from Allied Cementing (09/1985) shows 110 sx cement circulated from 400' through 1" tubing.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/09/2017 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated 810' and 1250'. Ran tubing to 2350' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1200' and pumped 75 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 15 sx cement at 300 psi. Hole standing full. Braden head full of cement.

GPS: 38.84843 -098.77287

Perfs:

Top	Bot	Thru	Comments
2391	2418		

INVOICED
JUN 27 2017

Remarks: QUALITY CEMENTING TICKET # 024

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) CM

KCC WICHITA
JUN 02 2017
RECEIVED