

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20862-00-00
Spot: NWSWSWSE Sec/Twnshp/Rge: 34-17S-8W
608 feet from S Section Line, 2344 feet from E Section Line
Lease Name: EDWARDS Well #: 1
County: ELLSWORTH Total Vertical Depth: 3245 feet

Operator License No.: 6988
Op Name: SMITH, RICHARD E. DBA SMITH OIL O
Address: 410 N. ADAMS PO BOX 550
HUTCHINSON, KS 67504

String	Size	Depth (ft)	Pulled (ft)	Comments
HOLI	5.5	2600		
PROD	5.5	3243		100 SX
SURF	8.625	331		185 SX
TI	2.5	1293		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/07/2017 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC. Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/08/2017 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL REDA PUMP OUT OF HOLE. ATTEMPT TO SET CIBP - HAD CASING PART AT 2600'. RUN TUBING TO BOTTOM AT 3240' AND SPOTTED 35 SX'S COMMON CEMENT WITH HULLS. ATTEMPT TO PULL TUBING UP TO 2600', COULD NOT - TUBING WAS STUCK. PUMPED ANOTHER 40 SX'S COMMON CEMENT. SHOOT TUBING OFF AT 1293' AND PULL TO 1100'. PUMPED 35 SX'S COMMON WITH 3 % CC. PULLED 35 SX'S COMMON WITH 3 % CC. PULLED TUBING OUT AND WAITED OVERNIGHT. TAGGED CEMENT IN A.M. ON 6-8-17 AT 900'. SET TUBING AT 750' AND PUMPED 35 SX'S COMMON WITH 3% CC, PULLED TUBING TO 380' AND CIRCULATED CEMENT TO SURFACE FROM BOTH CASINGS. PULLED TUBING OUT AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
3243	3245	OH	

INVOICED
JUN 27 2017

Remarks: COPELAND CEMENT #C-45311 TA - N.O.V. WELL.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)