

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21435-00-00
Spot: NWNESENW Sec/Twnshp/Rge: 15-7S-28W
1385 feet from N Section Line, 2072 feet from W Section Line
Lease Name: MOSS Well #: 1-15
County: SHERIDAN Total Vertical Depth: 4570 feet

Operator License No.: 35245
Op Name: SUEMAUR EXPLORATION & PRODUCT
Address: 539 N. CARANCAHUA SUITE 1100
CORPUS CHRISTI, TX 78401

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	302		280 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/23/2017 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: KELLY Company: MURFIN DRILLING CO., INC. Phone: (785) 769-6103

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 04/23/2017 3:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2550 w/50 sx
2nd plug @1700 w/100 sx
3rd plug @350 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed _____

Received
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

INVOICED
JUN 27 2017

MAY 04 2017

JUN 02 2017
CONSERVATION DIVISION
WICHITA, KS