

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-21640-00-00  
Spot: SENENWNW Sec/Twnshp/Rge: 26-25S-9W  
410 feet from N Section Line, 1060 feet from W Section Line  
Lease Name: POTTER & ISAACS 2509 Well #: 26-1  
County: RENO Total Vertical Depth: 5000 feet

Operator License No.: 35053  
Op Name: TAPSTONE ENERGY, LLC  
Address: PO BOX 1608  
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	18	63		19 SX CEMENT
	11	7	4337	350 SX
PROD	7	4337		350 SX
SURF	9.625	370		270 SX
TI	3.5	4283		

Well Type: SWD UIC Docket No: D31934.0 Date/Time to Plug: 04/14/2017 8:00 AM  
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC  
Proposal Revd. from: RANDY Company: Phone:

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/14/2017 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:


A CIBP WAS SET AT 4300', TUBING WAS RUN TO TOP OF B.P. WHERE MUD WAS CIRCULATED TO SURFACE. 25 SX CEMENT WAS ON TOP OF B.P. CASING WAS PULLED FROM 1000' AND LAYED OUT. TUBING WAS RUN TO 1400' WHERE 35 SX OF CEMENT WAS SPOTTED. PULLED TUBING TO 750' & SPOTTED 50 SX CEMENT. PULLED TUBING TO 430' & CIRCULATED CEMENT TO SURFACE.

Remarks: BASIC CEMENT. COMMON CEMENT. DENIED TA

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED  
JUN 27 2017