

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-02949-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 26-14S-16W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HEYL Well #: 3  
County: ELLIS Total Vertical Depth: 3353 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3350		150 SX
SURF	8.625	753		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2017 8:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Production perforations: 3041' - 3347'.  
Plugging Will run tubing to plug.  
Method: No well records. Need to perforate Anhydrite and 20' above base of surface pipe.  
Ordered 350 sx 60/40 pozmix 4% gel cement, 1500 # gel and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2017 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 920' (Anhydrite) and 730' (surface pipe). Ran tubing to 3290'.  
Quality Oil Well Cementing pumped 1500 # gel followed by 75 sx cement w/300 # hulls.  
Pulled tubing to 1000' and pumped 100 sx cement w/200 # hulls. Cement circulated out 5 1/2"  
casing. No returns on 8 5/8" surface pipe. PTOH. Topped off casing with 10 sx cement.  
Hooked up to 8 5/8" surface pipe with instant pressure.

Perfs:

Top	Bot	Thru	Comments
3320	3347		
3112	3259		
3041	3044		

Remarks: QUALITY OIL WELL CEMENTING

Plugged through: TBG

INVOICED  
JUN 27 2017

District: 04

Signed



(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JUN 16 2017

CONSERVATION DIVISION  
WICHITA, KS