

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-031-19096-00-00
Spot: NWSENWNW Sec/Twnshp/Rge: 14-23S-13E
4576 feet from S Section Line, 4576 feet from E Section Line
Lease Name: OLINGER A Well #: 5M
County: COFFEY Total Vertical Depth: 1836 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comment
<u>32044</u>	PROD	4.5	1825		20 SX
Op Name: <u>TRIMBLE & MACLASKEY OIL LLC</u>	SURF	7	36		20 SX
Address: <u>110 SOUTH ST PO BOX 171</u> <u>GRIDLEY, KS 66852</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2017 9:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: JIM THWEATT Company: _____ Phone: (620) 836-2000

Proposed Plugging Method: Cement plug at 1820ft, perf casing at 850ft and and 250ft, cement plug at 850ft, and cement from 250ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 06/15/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1802', pumped 15 sxs cement, pulled tubing to 864', pumped 15 sxs cement, pulled tubing to 250', pumped 90 sxs cement to surface, gel spacers between cement plugs, casing shot @ 864' & 250'.

Perfs:

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

RECEIVED
KCC DIST # 3
JUN 20 2017
CHANUTE, KS

MH

INVOICED
JUN 27 2017

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3389**
 Foreman Kevin McCoy
 Camp EUREKA

API # 15-031-19096-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
6-15-17	1000	OLINGERA #5M	14	23S	13E	COFFEY	KS
Customer		Safety Meeting		Unit #	Driver	Unit #	Driver
Trimble & MacLasky OIL LLC		KM		102	RICK L.		
Mailing Address		RL		110	JASON H.		
P.O. Box 171		JH		145	STEVE M.		
City		State	Zip Code				
Gridley		KS	66852				

Job Type P.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: Ran 2 3/8 Tubing Spot Cement Plugs as following in 4 1/2 casing.

15 SKS @ 1802'

Gel SPACER

15 SKS @ 864'

Gel SPACER

90 SKS FROM 250' TO SURFACE (INSIDE & OUT OF 4 1/2)

Note: 4 1/2 Perforated @ 850' & 250' For Plugging Procedures.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	.30	Mileage	3.95	118.50
C 203	120 SKS	60/40 Pozmix Cement	12.75	1530.00
C 206	415 *	Gel 4%	.20 *	83.00
C 206	400 *	Gel SPACER	.20 *	80.00
C 214	40 *	HULL	.45 *	18.00
C 108	5.16 Tons	Ton Mileage	M/C	345.00
C 113	4 HRS	80 BBL VAC TRUCK	85.00	340.00
C 224	3000 gals	CITY WATER	10.00/1000	30.00
<u>THANK YOU</u>			Sub Total	3294.50
			Less 5%	175.43
			Sales Tax	214.14
			6.5%	

Authorization Witnessed By BRIAN Title _____ Total **3333.21**

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.