

TO:

API Well Number: 15-207-21392-00-00

Spot: NENESWSE

Sec/Twnshp/Rge: 5-24S-14E

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

1301 feet from S Section Line, 1325 feet from E Section Line

Lease Name: PHIL BIRK

Well #: 10

County: WOODSON

Total Vertical Depth: 1758 feet

Operator License No.: 32044

Op Name: TRIMBLE & MACLASKEY OIL LLC

Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1758		35 SX
SURF	8	40		30 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/12/2017 9:00 AM

Plug Co. License No.: 32044

Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC

Proposal Rcvd. from: JIM THWEATT

Company:

Phone: (620) 836-2000

Proposed
Plugging
Method:

Perforate at 450ft and 250ft. 50 ft cement plug at 1758. 50 ft cement plug at 450 ft. Cement plug at 250 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: NONE

Date/Time Plugging Completed: 06/12/2017 11:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1707', pumped 15 sxs cement, pulled tubing to 450', pumped 15 sxs cement, pulled tubing to 250' pumped 45 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1728	1739		
RECEIVED KCC DIST # 3 JUN 13 2017 CHANUTE, KS <i>MH</i> INVOICED JUN 27 2017			

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUN 15 2017

CONSERVATION DIVISION
WICHITA, KS

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3347**
 Foreman Kevin McCoy
 Camp EUREKA

API # 15-207-21392-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
6-12-17	1000	Phil Birk # 10	5	24S	14E	Woodson	KS	
Customer <u>Trimble & MacLuskey OIL LLC</u>			Safety Meeting <u>KM RL JH 2A</u>		Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 171</u>					<u>102</u>	<u>RICK L.</u>		
City <u>Gridley</u>			State <u>KS</u>		<u>110</u>	<u>JASON H.</u>		
Zip Code <u>66852</u>					<u>141</u>	<u>Zevi A.</u>		

Job Type Plug old well Hole Depth _____ Slurry Vol. _____ Tubing 2-3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting: Top PERF OF Production Zone @ 1728' 4 1/2" Also Perforated @ 450' & 250' For Plugging Procedures. Ran 2-3/8 Tubing & Plug well as following.

15 SKS @ 1707'
Gel SPACER
15 SKS @ 450'
Gel SPACER
45' SKS FROM 250' to SURFACE (inside & out of 4 1/2")

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	30	Mileage	3.95	118.50
C 203	75 SKS	60/40 Pozmix Cement	12.75	956.25
C 206	260 #	Gel 4%	.20 #	52.00
C 206	500 #	Gel SPACER	.20 #	100.00
C 214	40 #	Hulls	.45 #	18.00
C 108	3.22 Tons	Ton Mileage	M/C	345.00
C 113	3 Hrs	80 BBL VAC TRUCK	85.00	255.00
C 224	3300 gals	City water	10.00/1000	33.00
Received KANSAS CORPORATION COMMISSION				
JUN 15 2017				
CONSERVATION DIVISION WICHITA, KS				
THANK You JA			Sub Total	2627.75
			Less 5% Sales Tax	141.24
			7.5%	197.08

Authorization witnessed By BRYAN Title _____ Total 2683.59

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.