

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19610-00-00  
Spot: S2NESENE Sec/Twnshp/Rge: 7-25S-5E  
3465 feet from S Section Line, 323 feet from E Section Line  
Lease Name: WILSON A Well #: 215  
County: BUTLER Total Vertical Depth: 2046 feet

Operator License No.: <u>5030</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>VESS OIL CORPORATION</u>	CIBP	4.5	1650		
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>	SURF	6.625	1988		70 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2017 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORP Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/23/2017 1:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CEMENT IN LINE @ 438'. PRESSURED WELL @ 500 LB & WELL BLED OFF SLOWLY. RIH IN WIRELINE, PERFORATED SQUEEZE HOLES @ 250-251' (4 HOLES). RIH W/ TUBING & TAGGED CEMENT, W/TUBING @ 435. QUE MIXED & PUMPED 37 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. LAYED DOWN TUBING, SWEDGED INTO 4 1/2" & SQUEEZED 3 SXS. SIP 300#. CEMENT TICKET QUE #53363.	Perfs:			
	Top	Bot	Thru	Comments
	1988	2046	OH	
1741	1770	OH		

INVOICED  
JUN 27 2017

Remarks: FAILED - REWORK/ SQUEEZE HOLES 1450. DID NOT DRILL OUT CEMENT. BACKSIDE FULL W/ CEMENT.  
Plugged through:

District: 02 Signed DUANE KRUEGER  
(TECHNICIAN)

18