

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-23043-00-00  
Spot: SWSNWSE Sec/Twnshp/Rge: 35-6S-21W  
1610 feet from S Section Line, 1940 feet from E Section Line  
Lease Name: STATES Well #: 2  
County: GRAHAM Total Vertical Depth: 3745 feet

Operator License No.: 34559  
Op Name: WM KS ENERGY RESOURCES LLC  
Address: 400 TEXAS STREET SUITE 600  
SHREVEPORT, LA 71101

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3746		175 SX
SURF	8.625	212		170 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/09/2017 9:00 AM  
Plug Co. License No.: 35464 Plug Co. Name: NUSS WELL SERVICE, LLC  
Proposal Rcvd. from: TOM BERENS Company: WM KS ENERGY RESOURCES LLC Phone: (785) 688-4040

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix 4% gel cement, 8 sx gel and 300 # hulls.  
Perforations at 3492' - 3496', 3511' - 3514', 3604' - 3606', 3630' - 3633' and 3683' - 3686'.  
Port Collar at 1827' w/400 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/09/2017 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3607' and pumped 7 sx gel followed by 50 sx cement. Pulled tubing to 1900' and pumped 150 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 20 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.48548 -099.62726

Perfs:

Top	Bot	Thru	Comments
3683	3686		


INVOICED  
JUN 27 2017

Remarks: QUALITY CEMENT TICKET # 1563

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

JUN 16 2017

CONSERVATION DIVISION  
WICHITA, KS

JUN 13 2017