

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21051-00-00
Spot: SEWNENE Sec/Twnshp/Rge: 20-32S-19W
4665 feet from S Section Line, 964 feet from E Section Line
Lease Name: KACI Well #: 1
County: COMANCHE Total Vertical Depth: 5925 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5078		WITH 2 SX CMT
PROD	5.5	5330	3260	WITH 125 SX CMT
SURF	8.625	715		WITH 600 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/01/2017 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 5078' WITH 2 SX CMT. PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. PLUG AT 760' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 06/01/2017 5:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5078' WITH 2 SX CMT. 1ST PLUG AT 1040' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 40 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5190	5198		
5123	5130		

INVOICED
JUN 27 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
JUN 09 2017
KCC DODGE CITY

[Signature]

SA