

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21315-00-01
Spot: SENWSWSE Sec/Twnshp/Rge: 4-32S-19W
810 feet from S Section Line, 1982 feet from E Section Line
Lease Name: BIRD N Well #: 2
County: COMANCHE Total Vertical Depth: 5328 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4957		WITH 2 SX CMT
CIBP		5158		WITH 2 SX CMT
COND	13.375	220		WITH 300 SX CMT
PROD	4.5	5315	3270	WITH 200 SX CMT
SURF	8.625	695		WITH 335 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/24/2017 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 5158' WITH 2 SX CMT. CIBP @ 4957' WITH 2 SX CMT. PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. PLUG AT 740' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 05/24/2017 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5158' WITH 2 SX CMT. SET CIBP @ 4957' WITH 2 SX CMT. 1ST PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 25 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5208	5213		SPF
5007	5011		SPF

INVOICED
JUN 27 2017

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed _____

Signature
50A (TECHNICIAN)

RECEIVED
JUN 13 2017
KCC DODGE CITY *MP*