

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20981-00-00
Spot: NESENWSW Sec/Twship/Rge: 9-32S-19W
1741 feet from S Section Line, 4168 feet from E Section Line
Lease Name: LONG TWIN Well #: 1
County: COMANCHE Total Vertical Depth: 6020 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4912		WITH 2 SX CMT
PROD	5.5	5830	3270	WITH 250 SX CMT
SURF	8.625	713		WITH 325 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/26/2017 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4912' WITH 2 SX CMT. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 740' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 05/26/2017 2:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4912' WITH 2 SX CMT. 1ST PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 740' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 30 SX CMT. 4TH PLUG AT 40' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4962	4965		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

INVOICED
JUN-27 2017

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUN 13 2017
KCC DODGE CITY

Form CP-2/3