

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-23273-00-00  
Spot: NESENE Sec/Twnshp/Rge: 32-8S-17W  
1690 feet from N Section Line, 330 feet from E Section Line  
Lease Name: STAMPER E Well #: 5  
County: ROOKS Total Vertical Depth: 3450 feet

Operator License No.: 35250  
Op Name: WOODWAY OIL & GAS I, LLC  
Address: 4900 WOODWAY DR. SUITE 625  
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3443		145 SX
SURF	8.625	1286		475 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/08/2017 12:00 PM  
Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE  
Proposal Rcvd. from: KORY PFEIFER Company: WOODWAY OIL & GAS I, LLC DBA Phone: (785) 735-4598

Proposed Plugging Method: Ordered 700 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Casing leak above 1700'.  
Production perforations: 3156' - 3318'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 05/08/2017 2:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated 2 holes at 1250'. Ran tubing to 3100' and pumped 200 sx cement w/200 # hulls.  
Pulled tubing to 1300' and pumped 315 sx cement to circulate 5 1/2" casing to surface. Closed valve on 5 1/2" casing and pumped 25 sx cement to circulate 8 5/8" x 5 1/2" annulus to surface.  
Pulled all tubing. Hooked to 5 1/2" casing and pumped 50 sx cement to top off annulus. Shut in pressure 300 psi on 5 1/2" casing.

GPS: 39.31663N -099.23355W

Perfs:

Top	Bot	Thru	Comments
3318	3333		
3276	3286		
3210	3220		
3156	3161		

Remarks: QUALITY OILWELL CEMENTING TICKET # 157

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*  
(TECHNICIAN)

CM

KCC WICHITA

JUN 02 2017

RECEIVED

MAY 12 2017

INVOICED  
JUN 27 2017