

7-5-88

6 061537

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-24176.00.00
NW, SEC. 31, T 16 S, R 14 W/E
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Varah Well # A 1

Operator: American Warrior
Name & Address: Box 399
Garden City, Ks. 67846

County Barton 114.34
Well Total Depth 3518 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 12:00 PM Day: 5 Month: July Year: 19 88

Plugging proposal received from Roger Loesch

(company name) Kelso Casing Pulling Inc. (phone) _____

were: Order 125 sks 65/35 Poz 10% Gel 2% Econolite 5 sks Hulls.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:00 PM Day: 5 Month: July Year: 19 88

ACTUAL PLUGGING REPORT 8 5/8" set at 300' w/175 sks. 4 1/2" set at 3518' w/125 sks!

Plugged bottom w/sand and 4 sks cement to 3050'. Shot pipe two times and recovered 1560'.
Pumped in 8 5/8" 25 sks cement followed w/5 sks Hulls in 100 sks cement w/700 Psi.

Remarks: By Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-23-88
INV. NO. 21889
1266' Coverage

Signed Gilbert G. Scheck
(TECHNICIAN)

DB