

1-2

35
R

6 062302

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009.14200.00.01
SW _____, SEC. 5, T 16 S, R 14 W/E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5921

Lease Name Batt Well # 1

Operator: Jan Carroll

County Barton 111.21

Name & Address Box 1987

Well Total Depth 3422 feet

Great Bend, Ks. 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 362

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address Box 768 Great Bend, Ks. 67530

Company to plug at: Hour: 9:00 AM Day: 2 Month: Jan Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

were: Order 200 sks 60/40 pos 8% gel 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00AM Day: 2 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8 set at 362 w/290 sks. 4 1/2 set at 3422 w/150 sks.

Top perf at 3208. Plugged bottom w/sand and 5 sks cement to 3150.

Shot pipe one time and recovered 1829. Pumped in 8 5/8 25 sks cement followed w/5 sks hulls in 175 sks cement w/500 psi.

JAN 7 1991
1-7-91
CONSERVATION DIVISION
Wichita, Kansas

Remarks: By B. J. Services Ran line to 1500.

INVOICED

(Additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 2-11-91

Signed Gilbert G. Scheck
(TECHNICIAN) E.O.O.

INV. NO. 30643

Gilbert G. Scheck