

6 070259

Rec'd 11-27-84

15-009-214560001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NW NW NW, SEC. 15, T. 16 S, R. 13 W/X
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6284

Lease Name Michaelis Well # B-1

Operator: Vonfeldt Oil Operations

County Barton

Named Address 524 St. John

Well Total Depth 3400 feet

Russell, Ks. 67665

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well XXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Russell

Company to plug at: Hour: PM Day: 27 Month: November Year: 19 84

Plugging proposal received from Decon Pulley

(company name) Rockhold Engineering, Inc. (phone) (316) 792-2506

were: 8 5/8" 423' SP CUC w/225 sks cmt - 4 1/2" csg set @ 3380 ft w/150 ft w/150 sks cmt

Plug back @ 3300ft - top perfs' 3141 ft - 3145 ft and 3166 ft - 68 ft. Plug bottom

with 4 sks cmt sand to 3100 ft and w/4 sks cmt, shot csg (2) times - Recovered 2000 ft,

Order 170 sks 50/50 pozmix 4% gel 3% cal. cl. 15 sks gel, 5 sks hulls, and 8 5/8" plug-

pump in 8 5/8" plug- pump in 8 5/8" S.P. with pump truck.

Plugging Proposal Received by M. J. Schmidt
Date (TECHNICIAN)

Plugging Operations attended by Agent?: All XXX Part _____ None _____

Operations Completed: Hour: 4:05 PM Day: 27 Month: November Year: 19 84

ACTUAL PLUGGING REPORT Ordered 170 sks 50/50 pozmix 4% gel 3% cal. cl., 15 sks gel,

5 sks hulls, and 8 5/8" plug, pumped in 8 5/8" SP with pump truck. Pumped in 4 sks hulls -

7 sks gel - 1/2 sk hulls - 30 sks cmt 8 sks gel - 1/2 sk hulls - release plug and 140 sks

cmt. - max pressure 450 PSI cemented by Allied Cementing

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed M. J. Schmidt
(Doic) (TECHNICIAN) 11-30-84

