

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APT NUMBER 15

SE, Sec. 16, T 19 S, R 14 WE
330' feet from N S section line

330 feet from W E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5258

Lease Name Hiss Well # 1

Operator: Messman-Kennel Corp.
Name & Address 1432 K.S. B. & T Bldg. Wichita, Kas.
67202

County Barton

Well Total Depth 3552 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 15" S feet 474'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Mo. 67524

Company to plug at: Hour: 1:00 PM Day: 15 Month: 12 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 sacks 58 permit - 4.2. Sel. - 3.2. Sel. U., 5 sacks hulls, 15
sacks Sel. & 8 5/8" plug.

Signed Arthur L. Kelso
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:20 PM Day: 15 Month: 12 Year: 1982

ACTUAL PLUGGING REPORT 15"-474' S.P. case w/ cement. 7" set at 3225' w/ 150 sacks
cement. P.V. tool at 480' cement case to surface. 1 1/2" set at 3552' w/
150 sacks cement. Plug back to 3310'. Top perf. at 3252'. Plugged bottom
w/ 4 sacks cement, sand & 4 sacks cement to 3200'. Shot pipe 2 time & recovered
2828'. Pumped into 7", 25 sacks cement, 4 sacks hulls, 12 sacks Sel., 50 sacks cement,
3 sacks Sel., 1 sack hulls, released plug & followed w/ 90 sacks cement.

Remarks: Maximum pressure 700 pounds.

RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1982

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Arthur L. Kelso
(TECHNICIAN)

INVOICED
DATE 12-28-82
INV. NO. 2054-01