

6060310

15.009.01382.00.01

API NUMBER 15- 0WNO

SW, SEC. 16, T. 17 S, R. 14 W

990 feet from W/S section line

2970 feet from NE section line

Lease Name Kennedy Well # 2

County Barton

Well Total Depth 3473 112.87 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 895

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7844

Operator: Slivers Company

Name & Address Box 994

Great Bend, Mo.

67530

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Helco Casing Pulling License Number 6050

Address Box 176, Chase, Mo. 67524

Company to plug at: Hour: 11:00AM Day: 9 Month: Aug Year: 19 84

Plugging proposal received from Bob Brannaman

(company name) Helco Casing Pulling (phone) 316-938-2457

were: Order 1651.50 pozmix-6 lb sack-3 3/8 gal. U., 15 sb. Gels, 5 sb. bulls.
+ 8 5/8" plugs.

Plugging Proposal Received by Gallo de Sabel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 PM Day: 9 Month: Aug Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" - 895' conc. 4 1/2" set at 3472' w/ 150 sb.

Top perf. at 3223'. Plugged bottom w/ 4 sb. cement, sand & 4 sb. cement
to 3175'. Shot pipe 3 times & recovered 2418'. Pumped in
8 5/8" - 4 sb. bulls, 25 sb. cement, 12 sb. Gels, 40 sb. cement, 3 sb. Gels,
1 sb. bulls, released plug & followed w/ 100 sb. cement w/ 800 pounds
pressure.

Remarks: By Gallo
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1984
signed _____
(TECHNICIAN)

DATE 8-17-84

INV. NO. 3229

CONSERVATION DIVISION
Wichita, Kansas

8-10-84
31