



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

RECEIVED
STATE CORPORATION COMMISSION

AUG 19 1959

CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date August 13, 1959, authorized the following plugging operation:

Operator's Full Name: National Associated Petroleum Co.

Complete Address: 502 Ritz Bldg., Tulsa, Okla.

Lease Name: Mary T. Peiz PEIZ Well No. 1 "A"

Location: SW-NE-SW Sec. 12 Twp. 17 Rge. 14 (E) (W) X

County: Barton Total Depth: 3520

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 350' with heavy mud.
Push plug and 1/4 sacks hulls to 350' and cement with 25 sacks thru
drill pipe. Fill hole to 40' with heavy mud--set solid bridge--
cement with 10 sacks. Fill, bridge, cement rathole with 2 sacks.

Very truly yours,

Signed: Arthur J. Tomasz
 Conservation Division Agent