

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date January 23, 19 59, authorized the following plugging operation:

Operator's Full Name: Franco Central Oil Co.

Complete Address: 750 Fourth Natl. Bank Bldg., Wichita, Kansas

Lease Name: Steiner Well No. 1

Location: NW-NW-SW Sec. 34 Twp. 17 Rge. 12 (E) (W) x

County: Barton Total Depth: 3425.

Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

Gun bits and circulate heavy mud. Fill hole to 735' with heavy mud. Push plug and 1/2 sack hulls to 735' and cement with 20 sacks thru drill pipe. Fill hole to 310' with heavy mud--push plug and 1/2 sack hulls to 310' and cement with 20 sacks thru drill pipe. Fill hole to 40' with heavy mud--push plug and 1/2 sack hulls to 40' and cement with 10 sacks. Bridge, and cement rathole with 2 sacks.

RECEIVED STATE CORPORATION COMMISSION

Very truly yours, JAN 29 1959 CONSERVATION DIVISION Wichita, Kansas

Signed: [Signature] Conservation Division Agent