

15.009.14184.00.01

KANSAS

FORM CP-3
Rev, 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- - ✓

245 North Water
Wichita, KS 67202

Operator's Full Name Dean Allison Oil Co.

Complete Address 507 Insurance Bldg. Wichita, KS. 67202.

Lease Name Demel Well No. 1

Location NWSW NF Sec. 36 Twp. 17S Rge. 12 (~~East~~) (West)

County Barton Total Depth 3428

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, KS. 67524 License No. 683

Operation Completed: Hour 12¹⁵ Day 27 Month 4 Year 1981
PM

The above well was plugged as follows:

Sanded Back to 3350' & 45X Cement @ Dump Bailer.

Squeezed Thru. 8 5/8" Surface Casing with 400# Huls, 16sx

MudGel, 100# Huls, 25sx cement, 45X Mudgel, Plug & 100SX Cem.

Max. Pres. 1100# Shut in Pres 600#

Recovered 1886' of 4 1/2" casing

3394' of 4 1/2" casing cemented with 125sx cement.

271' of 8 5/8" Surface Casing Cement Circ.

I hereby certify that the above well was plugged as herein stated.

4-29-81
RECEIVED
STATE CORPORATION COMMISSION
APR 29 1981
CONSERVATION DIVISION
Wichita, Kansas

Signed: Drew Harkin
Conservation Division Agent

DATE 5-15-81

INV. NO. 5362-W

INVOICED