


STATE OF KANSAS
STATE CORPORATION COMMISSION

15.009.60013.00.00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Barton County. Sec. 6 Twp. 16S Rge. 12W (E) (W)
Location as "NE/CNW/SW/W" or footage from lines NE SE SE
Lease Owner Franco Central Oil Company
Lease Name Depiesse Well No. 9
Office Address Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 6 19 54
Application for plugging filed July 6 19 54
Application for plugging approved July 6 19 54
Plugging commenced July 6 19 54
Plugging completed July 6 19 54
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LOG ATTACHED						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 250', set plug with 1/2 sack
hulls and cemented with 20 sacks through drill pipe.
Filled hole with mud to 35', set plug and cemented
with 10 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Carl Todd Drilling Company
Address 404 KFH Building, Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. L. Livingston (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Livingston

SUBSCRIBED AND SWORN TO before me this 6th day of July, 1954

Rebecca Hill
Notary Public.

My commission expires Oct. 21, 1957



7-14-54

15.009.60013.00.00

THE CARL TODD DRILLING COMPANY
404 KFH Building
Wichita, Kansas

FRANCO CENTRAL OIL COMPANY
#9 Depiesse
NE SE SE Sec. 6-16S-12W
Barton County, Kansas

COMMENCED: June 27, 1954
COMPLETED: July 6, 1954

ELEVATION: 1841 Rotary Bushing

SURFACE CASING

0 - 10	Surface clay
10 - 45	Post Rock
45 - 130	Shale & shells
130 - 315	Shale & shells
315 - 338	Shale
338 - 450	Shale & iron stks
450 - 735	Red Bed and shale
735 - 785	Shale and Red Bed
785 - 810	Anhydrite
810 - 1185	Red Bed, shale & shells
1185 - 1285	Shale and shells
1285 - 1350	Shale and salt
1350 - 1485	Shale
1485 - 1690	Lime and shale
1690 - 1855	Lime and shale
1855 - 1995	Lime and shale
1995 - 2190	Shale and lime
2190 - 2385	Shale and lime
2385 - 2550	Shale
2550 - 2713	Shale and lime
2713 - 2725	Shale and lime
2725 - 2770	Lime
2770 - 2840	Lime
2840 - 2900	Lime
2900 - 2980	Lime
2980 - 3030	Lime
3030 - 3080	Lime
3080 - 3140	Lime
3140 - 3175	Lime
3175 - 3196	Lime
3196 - 3240	Lime
3240 - 3280	Lime
3280 - 3303	Lime
3303 - 3320	Lime
3320	Rotary Total Depth

8-5/8" OD 24# casing set at 338'
cemented with 200 sacks

TOPS

Topeka	2620
Heebner	2922
Toronto	2937
Brown Lime	3006
Lansing	3017
Arbuckle	3312

Drill Stem Test 3254 - 96
Open 30 min., recovered 30" mud,
BHP 490#

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By:

Carl Todd

RECEIVED
STATE COURT HOUSE
WICHITA, KANSAS
JUL 10 1954

PLUGGING			
FILE	SIC	6-16-R-12W	
BOOK	PAGE	46	LINE 40