

15.009.00687.00.00

# WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

OR

## FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW  
 Barton County. Sec. 6 Twp. 20 Rge. 12 ~~W~~ W (W)  
 Lease Owner Mouser Drilling Company  
 Lease Name Fransen Well No. 1  
 Office Address 515 Union Nat'l Bank Bldg. Wichita 2, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry  
 Date well completed December 17 1948  
 Application for plugging filed September 8 1949  
 Application for plugging approved September 9 1949  
 Plugging commenced " 1949  
 Plugging completed " 1949  
 Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas  
 Producing formation Arbuckle Depth to top Bottom Total Depth of Well Feet  
 Show depth and thickness of all water, oil and gas formations.

### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Pipe				8 5/8"	316'	Cemented
Oil String				5 1/2"	325 1/2'	2106'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rock from 3218' to 3160' - Dumped 5 sax cement at 3160' with dump bailer. Top of cement at 3125' - Mud from 3125' to 300', pumped plug to 300' with 100 sax cement.

RECEIVED

Conservation Div.  
 SEP 13 1949  
 STATE CORPORATION COMMISSION  
 KANSAS

9-13-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mouser Drilling Company  
 Address 515 Union National Bank Bldg. Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
B. L. Mouser (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
 (Signature) B. L. Mouser By: B. L. Mouser Partner  
515 Union Nat'l Bank Bldg. Wichita 2, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 12th day of September, 1949

James L. Walker  
 Notary Public.

My commission expires March 18, 1950

PLUGGING  
 FILE SEC 6 T 20 R 12  
 BOOK PAGE 113 LINE 11

Fransen No. 1 Well

Sec. 6-20S-12W, Barton County, Kansas

Drilled for: David Fransen  
Mouser Drilling Company  
Dave Ainsworth

Drilled by: Mouser Drilling Company

Drilling Commenced: December 4, 1948  
Drilling Completed: December 17, 1948

Casing Record

8 5/8" 316'  
5 1/2" 3254'

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5	Broken lime	2875
Clay and sand	35	Lime	3045
Sand	112	Lime and shale	3148
Iron and shale	120	Lime	3394
Iron	130	Conglomerate	3454
Shale	210	Arbuckle	3463
Red sand	260		
Red bed	651		
Anhydrite	675		
Red bed	906		
Shale and shells	1060		
Salt	1340		
Shale and shells	1510		
Lime and shale	1775		
Sand and lime	1795		
Shale and shells	1840		
Lime and shale	1965		
Lime	2010		
Lime and shale	2160		
Shale and shells	2475		
Lime and shale	2795		
		Total Depth	3463'
		Top K.C. Lime	3165'
		Top Conglomerate	3394'
		Arbuckle	3454-3463

STATE OF KANSAS

SS:

COUNTY OF SEDGWICK

I, RECEIVED being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the above described location to the best of my knowledge and belief.

SEP 13 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

Dr. Mouser

Subscribed and sworn to before me this 17th day of December 1948.

My Commission Expires:

March 18 1950

Francis G. Habber

PLUGGING  
FILE SEC 6-T-20-R-20  
BOOK PAGE 113 LINE 11