

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15.009.00851.00.00

WELL PLUGGING RECORD

NORTH

| | | | |
|--|---|--|--|
| | | | |
| | | | |
| | 0 | | |
| | | | |

Locate well correctly on above Section Plat

Barton County. Sec. 24 Twp. 20 Rge. (E) 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE/4 NE/4 SW/4
Lease Owner Musgrove Petroleum Corporation
Lease Name Maybach Well No. 1
Office Address 407 K.F.H. Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-3 19.50
Application for plugging filed 9-3 19.50
Application for plugging approved 9-3 19.50
Plugging commenced 9-3 19.50
Plugging completed 9-3 19.50
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3593 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 249' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was running full of water, plugged by setting Halliburton head in collar at bottom of cellar, and ran 70 sacks of cement under pressure in hole. Closed valve on head, cement filled 200 feet in hole.

9-16-50

RECEIVED

Conservation Div.

SEP 16 1950

STATION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Musgrove Petroleum Corporation
Address 407 K.F.H. Building
Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19.50.

Nadine J. Jurek

Notary Public.

My commission expires December 5, 1951

PLUGGING
FILE SEC 24 T 20 R 140
BOOK PAGE 25 LINE 22

COMPANY: Musgrove Petroleum Corporation Inc.
 CONTRACTOR: Jackson Drilling Corporation
 FARM: Maybach #1
 LOCATION: NE NE SW Section 24-20-14W
 Barton County, Kansas
 ELEVATION: 1893
 COMMENCED: August 17, 1950
 COMPLETED: September 3, 1950

| | | | |
|------|----|-----------|----------------|
| 0 | to | 260 | Shale |
| 260 | to | 365 | Sand |
| 365 | to | 795 | Red bed |
| 795 | to | 820 | Anhydrite |
| 820 | to | 1585 | Shale & shells |
| 1585 | to | 1834 | Lime & shale |
| 1834 | to | 1945 | Lime |
| 1945 | to | 2720 | Shale & lime |
| 2720 | to | 2963 | Lime & shale |
| 2963 | to | 3052 | Lime |
| 3052 | to | 3120 | Lime & shale |
| 3120 | to | 3170 | Lime |
| 3170 | to | 3245 | Lime & shale |
| 3245 | to | 3250 | Shale |
| 3250 | to | 3268 | Brown lime |
| 3268 | to | 3292 | Lime |
| 3292 | to | 3315 | Lime & shale |
| 3315 | to | 3510 | Lime |
| 3510 | to | 3535 | Conglomerate |
| 3535 | to | 3595 | Lime |
| | | 3595 T.D. | |

8 5/8" casing set at 252 feet. Cemented with 150 sacks cement and 2 sacks calcium chloride.

Dry

All measurements from top of derrick floor.

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the Maybach #1, Section 24-20-14W, Barton County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 8th day of September, 1950.

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950.

PLUGGING
 WELL SEC 20 T 20 14W
 BOOK PAGE 25 LINE 22